


Toilet Works in the office of the Vice Chancellor						
Sl. No.	Sub-Heads and Items of Works	Unit	Quantity	Rate in Figure	Rate in Words	Amount
	Vice Chancellor's Office					
	Toilet Works					
2	Providing and fixing Vanity Basin 32 * Aber with 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require:	each	1			
3	Providing and fixing jaquar selfy shower pannel anti finger with all necessary fitting wherever require:	each	1			
4	Providing and fixing Wall hung WC Rimless ,blind with UF soft close slim seat ver,hiiges,accessories set.KUS-WHM-35953BISUF5M, cutting and making good the walls wherever require:	each	1			
5	Providing and fixing SINGLE PIECE SLIM CONCEALED CISTERN WITH FLOOR MOUNTING FRAMEset.JCS-WHT-2400FS , cutting and making good the walls wherever require:	each	1			
6	Providing and fixing AO SMITH INSTANT GEYSER 3LTR	each	1			
7	Providing and fixing Urinal partition plate	each	3			
8	Providing and fixing Pvc Automatic Hand Dryer	each	1			
9	Providing and fixing Toughened Glass Panes in exising door	sqm	2.1			
10	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete.					
	Flexible pipe 32 mm dia	Each	8			
11	Providing and fixing C.P. brass long nose bib cock of approved quality conforming to IS standards and weighing not less than 810 gms.					
	15 mm nominal bore	Each	5			
12	Providing and fixing C.P. brass stop cock (concealed) of standard design and of approved make conforming to IS:8931.					
	15 mm nominal bore	Each	7			
13	Providing and fixing mirror of superior glass (of approved quality) and of required shape and size with plastic moulded frame of approved make and shade with 6 mm thick hard board backing :					
	Oval shape 450x350 mm (outer dimensions)	nos	1			

Toilet Works in the office of the Vice Chancellor						
Sl. No.	Sub-Heads and Items of Works	Unit	Quantity	Rate in Figure	Rate in Words	Amount
14	Providing and fixing PTMT towel rail complete with brackets fixed to wooden cleats with CP brass screws with concealed fittings arrangement of approved quality and colour.					
	600 mm long towel rail with total length of 645 mm, width 78 mm and effective height of 88 mm, weighing not less than 190 gms.	each	5			
15	Making the opening in brick masonry including dismantling in floor or walls by cutting masonry and making good the damages to walls, flooring and jambs complete, to match existing surface i/c disposal of mulba/ rubbish to the nearest municipal dumping ground, all complete as per direction of Engineer-in-Charge.					
	For door/ window/ clerestory window	sqm	7.3			
16	Fixing chowkhats in existing opening including embedding chowkhats in floors or walls cutting masonry for holdfasts, embedding hold fasts in cement concrete blocks of size 15 x 10 x 10 cm with cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size), painting two coats of approved wood preservative to sides of chowkhats and making good the damages to walls and floors as required complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge.					
	Door chowkhats	each	2			
17	Providing and fixing factory made single extruded WPC (Wood Polymer Composite) solid door/window/Ceostory windows & other Frames/Chowkhat comprising of virgin PVC polymer of K value 58-60 (Suspension Grade), calcium carbonate and natural fibers (wood powder/ rice husk/wheat husk) and non toxic additives (maximum toxicity index of 12 for 100 gms) fabricated with miter joints after applying PVC solvent cement and screwed with full body threaded star headed SS screws having minimum frame density of 750 kg/cum, screw withdrawal strength of 2200 N (Face) & 1100 N (Edge), minimum compressive strength of 58 N/mm ² , modulus of elasticity 900 N/mm ² and resistance to spread of flame of Class A category with property of being termite/borer proof, water/moisture proof and fire retardant and fixed in position with M.S hold fast/lugs/SS dash fasteners of required dia and length complete as per direction of Engineer-In-Charge. (M.S hold fast/lugs or SS dash fasteners shall be paid for separately). Note: For WPC solid door/window frames, minus 5mm tolerance in dimensions i.e depth and width of profile shall be acceptable. Variation in profile dimensions on plus side shall be acceptable but no extra payment on this account shall be made.					

Toilet Works in the office of the Vice Chancellor

Sl. No.	Sub-Heads and Items of Works	Unit	Quantity	Rate in Figure	Rate in Words	Amount
	Frame size 65 x 125 mm	metre	5.32			
18	Providing and fixing mirror of superior glass (of approved quality) and of required shape and size with plastic moulded frame of approved make and shade with 6 mm thick hard board backing :					
	Circular shape 450 mm dia	each	4			
19	Rectangular shape 453x357 mm	each	6			
20	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead.					
	For thickness of tiles above 25 mm and up to 40 mm	sqm	36.3			
21	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3 kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	sqm	27.69			
22	Providing and laying rectified Glazed Ceramic floor tiles of size 300x300 mm or more (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in all colours, shades, except White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick Cement Mortar 1:4 (1 Cement : 4 Coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including pointing the joints with white cement and matching pigments etc., complete.	sqm	8.61			
23	15 mm cement plaster on the rough side of single or half brick wall of mix 1:6 (1 cement: 6 fine sand)	sqm	10.76			
Grand Total						
SAY=						
RupeesOnly						





Sealed Signature of the Tenderer
Date