

INTERIOR PLANNING, DESIGNING AND CONSTRUCTION OF THE ROOMS OF REGISTRAR, DEAN (R&D), ACADEMIC REGISTRAR, FINANCE OFFICER OF COTTON UNIVERSITY AT PAN BAZAR, GUWAHATI, ASSAM

Sl. No.	Sub-Heads and Items of Works	Unit	Quantity	Rate in Figure	Rate in Words	Amount
	Registrar Office					
	Low height storage					
1	Providing and constructing overhead and low height storage of width 400mm and size as per drawings, with top, sides and bottom in 19mm thick marine grade plywood, back in 6mm thick marine ply, intermediate in 19mm thick marine grade plywood, Shutters in 19mm block board.. All external surfaces to be finished in approved 1mm thick laminate, with balancing anamel painting on the interior surface. All exposed edges to be finished in 1mm thick laminate. Rate to include hardware such as approved locks, auto closing hinges for shutters, approved handles, door stop, tower bolt, etc. complete as specified and directed.	Sq.M.	7.37			
	Panelling Works					
2	Providing, Fixing and Finishing 12mm / 19mm / 6mm Plyboard Panelling of required thickness fixed over brick wall / Sal Wood Frame of size 50mm x 38mm & 50mm x 50mm made of required section as per design finished with 1mm Laminate as specified, complete with necessary hardwares and fittings	Sq.M.	13.28			
	Decorative Door					
3	Finishing of existing Door bothside with 6mm Plyboard Pasting and 1mm decorative laminate Pasting, finished with PU polish as per desired colour and shade as per Archietcts instructions and provided with Concealed Door Closure, Magnetic Door Stopper, 125mm long 2.9mm thick Heavy Duty S.S Bearing Hinge, Mortice Lock with Handle (All fittings to be of DORMA make as specified in the drawings), complete with all other necessary hardwares as per design, specified and directed by the department/consultant.	Sq.M.	1.40			
	ACADEMIC REGISTRAR'S OFFICE					
	Decorative Door					

INTERIOR PLANNING, DESIGNING AND CONSTRUCTION OF THE ROOMS OF REGISTRAR, DEAN (R&D), ACADEMIC REGISTRAR, FINANCE OFFICER OF COTTON UNIVERSITY AT PAN BAZAR, GUWAHATI, ASSAM

Sl. No.	Sub-Heads and Items of Works	Unit	Quantity	Rate in Figure	Rate in Words	Amount
6	Providing & Finishing of 35mm thick flush Door bothside with 6mm Plyboard Pasting and 1mm decorative laminate Pasting, finished with PU polish as per desired colour and shade as per Archietcts instructions and provided with Concealed Door Closure, Magnetic Door Stopper, 125mm long 2.9mm thick Heavy Duty S.S Bearing Hinge, Mortice Lock with Handle (All fittings to be of DORMA make as specified in the drawings), complete with all other necessary hardwares as per design, specified and directed by the department/consultant.	Sq.M.	1.80			
	Low helght storage					
7	Providing and constructing overhead and low height storage of width 400mm and size as per drawings, with top, sides and bottom in 19mm thick marine grade plywood, back in 6mm thick marine ply, intermediate in 19mm thick marine grade plywood. Shutters in 19mm block board.. All external surfaces to be finished in approved 1mm thick laminate, with balancing anamel painting on the interior surface. All exposed edges to be finished in 1mm thick laminate. Rate to include hardware such as approved locks, auto closing hinges for shutters, approved handles, door stop, tower bolt, etc. complete as specified and directed.	Sq.M.	6.24			
	Total					

Rupees Only

[Handwritten signatures]

Sealed Signature of the Tenderer

[Handwritten signature]