



COTTON UNIVERSITY

Panbazar, Guwahati, Assam-781001

www.cottonuniversity.ac.in :: 0361-2733530 :: registrar@www.cottonuniversity.ac.in

No. CU/EC/2017/025/PART-1

Dated:

NOTICE INVITING TENDER

NIT No: 16 of 2025-26

Web Notice

Cotton University invites sealed bid in Single bid systems from the interested empanelled contractors for the following works.


Package	Name of the work	Amount (in Rs.)
A	Renovation Girls & Boys Toilet 3 rd Floor above 210 room no, MCB Building, CU	RS.1,19,229.00

Detailed tender may be downloaded from the university website from 08/09/2025 onwards. The last date of submission of sealed tender to the office of the undersigned is 15/09/2025 till 14:00 hrs. If for any reason, last date of receiving and opening of tender is declared a holiday, the same will be received and opened in the next working day.

All the rates will be inclusive of all taxes and duties.

The Registrar, Cotton University reserves the rights to accept or reject any/all the bid(s) without assigning any reason thereof.

The web Notice will be a part of the Bidding Documents.


Registrar
Cotton University


Memo No. CU/EC/2017/025/PART-1/5452-55

Dated: 08/09/25

Copy for information to:

1. PS to the Vice Chancellor for kind information of Hon'ble Vice Chancellor.
2. Finance Officer, CU
3. System Manager, CU for uploading the entire bid document in University website.
4. Relevant Office files.




Registrar
Cotton University

Price Bid

Mame of work: Renovation Girls and Boys Toilet 3rd Floor above 210 room no, MCB Building, Cotton University						
NIT NO: 16 Of 2025/26 Dated 05/09/2025						
S/L NO	ITEM OF WORK	UNIT	QUANTITY	RATE	RATE IN FIGURE	AMOUNT
1	Dismantling old C.I. pipes including excavation and refilling trenches after taking out the pipes, breaking lead caulked joints, melting of lead and making into blocks, including stacking of pipes at site lead up to 50 metre:					
	100 mm diameter C.I. pipe	Meter	27.00			
2	Dismantling G.I. pipes (external work) including excavation and refilling trenches after taking out the pipes, manually/ by mechanical means including stacking of pipes within 50 metres lead as per direction of Engineer-in-charge :					
	15 mm to 40 mm nominal bore	Meter	15.00			
3	Dismantling of flushing cistern of all types (C.I./PVC/Vitrious China) including stacking of useful materials near the site and disposal of unserviceable materials within 50 metres lead.	Each	2.00			

[Signature]

[Signature]

	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge.Externa work						
4	25 mm nominal dia Pipes	Meter	15.00				
5	100 mm nominal dia Pipes	Meter	12.00				
	Providing and fixing controlled flush, low level cistern made of vitreous china with all fittings complete.						
6	10 litre (full flush) capacity-white	Each	2.00				
	15 mm cement plaster on the rough side of single or half brick wall of						


✓

✓

7	1:4 (1 cement: 4 fine sand)	Sqm	18.00			
8	Cement mortar 1:4 (1 cement : 4 coarse sand)	cum	4.00			
9	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. For thickness of tiles 10 mm to 25 mm					
10	Providing and laying in position ready mixed or site batched design mix cement concrete for plain cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana/Ordinary Portland /Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting	Sqm	45.00			

	of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering and finishing as per direction of the engineer-in-charge; for the following grades of concrete. Note: Extra cement up to 10% of the minimum specified cement content in design mix shall be payable separately. In case the cement content in design mix is more than 110% of the minimum specified cement content, the contractor shall have discretion to either re-design the mix or bear the cost of extra cement.	CUM	1.14				
11	Providing and fixing water closet squatting pan (Indian type W.C. pan) with 100 mm sand cast Iron P or S trap, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required:						





W.C. pan with ISI marked white solid plastic seat and lid	Each	2.00				
					TOTAL=	

[Handwritten signature]

[Handwritten signature]